


SECTION VIEW

(PAVED AREAS)
12" THICKNESS SF 9.5A OR B,
BASE COURSE OR
CONCRETE PAD



PLAN VIEW

- NOTES:**
1. ALL VALVE BOXES SHALL BE TWO PIECE. WHEN ALLOWED BY THE TOWN ENGINEER, MANUFACTURED VALVE BOX EXTENSIONS SHALL BE USED. CUT EXTENSIONS OR PIPE SHALL NOT BE ALLOWED.
 2. VALVE OPERATING NUT MUST BE EXTENDED SO THAT THE DEPTH IS NO GREATER THAN 5' (ft.) FROM THE SURFACE USING A MANUFACTURER APPROVED EXTENSION KIT.
 3. PRECAST CONCRETE ENCASUREMENT IS ALLOWED OUTSIDE OF PAVED AREAS.
 3. WHEN VALVE IS ADJACENT TO TEE OR BEND, ANCHOR VALVE TO TEE OR BEND, ANCHOR VALVE TO TEE OR BEND WITH TWO (2) 3/4" ALL THREADED RODS.

SCREW TYPE CAST
IRON VALVE BOX

NOTE TO CONTRACTOR:
VALVE BOX SHOULD NOT
CONTACT MAIN OR VALVE.